



Kotahimai Rural Municipality
Office of Rural Municipal Executive
Majhgawa, Rupandehi, Nepal.

Invitation for Bids

First Date of Publication: **14/Jestha /2083**

1. Kotahimai Rural Municipality has allocated funds towards the cost of procurement of works and intends to apply part of the funds to cover eligible payments under the following Contract.

S N	Contract ID	Description of Works	Grand Estimated Amount Nrs. (Including VAT and Others) Nrs.	Bid Security Amount & Bid Security Validity Period	Bidding Process
1	01/W/Q/KRM/082/083	Gohin Gau bhitra adhuro PCC dhalan dekhi Paschim jane bato PCC dhalan, Ward 1	1000000	Nrs.25000 75 Days	Quotation
2	02/W/Q/KRM/082/083	Amarganj Rambrikshako Ghar dekhi Taulan ko ghar samma PCC dhalan, Ward 1	1000000	Nrs.25000 75 Days	Quotation
3	03/W/Q/KRM/082/083	Patijiya Aduro Durga Mandir Nirman , Ward 1	1000000	Nrs.25000 75 Days	Quotation
4	04/W/Q/KRM/082/083	Jamuhi dekhi Lu.Sa.Na.Pa ko simana ra purnihawa chowk dekhi sano sipawa sadak starunnati, Ward 1	1000000	Nrs.25000 75 Days	Quotation
5	05/W/Q/KRM/082/083	Health post ma Bharyang tatha Ramp Nirman , Ward 1	1000000	Nrs.25000 75 Days	Quotation
6	06/W/Q/KRM/082/083	Ward 5 office agadi bato starunnati ra Marchawar Adarsha Mabi ma mato patan ra gravel	775000	Nrs.25000 75 Days	Quotation
7	07/W/Q/KRM/082/083	Thulo Majhgawa Madarsha dekhi Main sadak sano majhgawa hudai Lodhpurwa Sadak Gravel, ward 5	800000	Nrs.25000 75 Days	Quotation
8	08/W/Q/KRM/082/083	Gaunpalika Sabha Hall Pachadi hudai palika jane bato nirman tatha gravel ra lodhpurwa Krishi bato sadak gravel, ward 5	1000000	Nrs.25000 75 Days	Quotation

2. Eligible bidders can inspect the BoQ at the website of Kotahimai Rural Municipality Office <http://kotahimaimun.gov.np/>. Please download the whole document and fill Quotation submission form and particular Boq and submit it (Quotation submission form and BoQ) in office by hand. The submitted quotation should generally be signed, sealed, and submitted in the prescribed below **Quotation Submission Form**

3. Bid Submission, Bid Opening & Bank Details :

Last date and Time of Bid Submission	Bid opening date and Time	Bank Account Details		
		Office Name	Bank Name /Address	Bid security
21 Jestha 2083; 12:00 Hours	21 Jestha ; 1:00 Hours	Kotahimai Rural Municipality	Agricultural Develoment Bank/ Majhgawa, Rupandehi	0414101151094034 (Ga.3) (Dharauti Khata) for cash. Bank guarantee is also permitted.

4. Matters not covered in this notice shall be in accordance with prevailing rules and regulations , PPA 2063 and PPR 2064 and other related acts of Nepal.

5. Any amendment in the notice or BoQ will be posted in Office's Web site <http://kotahimaimun.gov.np/>

6. The employer reserves the right to accept or reject, wholly or partly any or all the bids without assigning reason whatsoever.

Chief Administrative Officer

Quotation Submission Form

Date :

To
Office of the Rural Municipal Executive
Kotahimai Rural Municipality
Majhgawa, Rupandehi

Subject: Submission of Quotation

Dear Sir/Madam,

With reference to your quotation notice published for the work,

Name of Work:.....

Quotation Number.....

we hereby submit our quotation as per the prescribed terms and conditions. Our quotation details are as follows:

- Name of Firm/Company:
- Address:
- Contact No.:
- PAN/VAT No.:
- Quotation (quoted) Amount: Rs. (with Vat and PS)
- Amount in Words: (with Vat and Ps)

We have enclosed the following documents along with the quotation:

1. Firm Registration Certificate
2. PAN/VAT Registration Certificate
3. Tax Clearance Certificate
4. Quotation/Bill of Quantity
5. Bid Security/Earnest Money Deposit
6. Construction Business License
7. Quotation/BOQ

We hereby declare that:

- We agree to abide by all terms and conditions mentioned in the quotation document.
- We understand that the Rural Municipality reserves the right to accept or reject any quotation wholly or partially without assigning any reason whatsoever.

We assure you that the work shall be completed as per the specifications and within the stipulated time if awarded to us.

Thank you.

Yours faithfully,

.....
Authorized Signature

Name: _____

Designation: _____

For: [Firm/Company Name.....]

Date: _____

Seal of Firm/Company

Q No.:

01/10/8/1/KRM/082/083



Kotahimai Rural Municipality
Office of Kotahimai Rural Municipality Executive
Majhagawa, Rupandehi
Lumbini province
Bill Of Quantity

(Signature)
Majhagawa, Rupandehi

Project Name: Gohun Gaun Bhitra PCC Dhalan Bhitra Adhuro PCC Dhalan Dekri Paschim Jane Bato PCC Dhalan
Location :- KRM W.N. - 1

F. Y. : - 2082/083

Date: 2083/01/02

S.n.	Description of work	Quantity	Unit	Rate	Rate In Word	Amount	Remark
CONSTRUCTION WORKS							
1	Loosening of the ground upto a level of 200-250mm below the sub-grade level and compacted in layers as per Drawing and Technical Specification (compacting original ground supporting sub-grade)(1003/1005)	495.90	sqm				
2	Providing and laying loose gravel on the surface.	37.19	cum				
3	Providing and laying of PCC (Grade M 15) in Road complete as per Drawing and Technical Specifications(2000)	74.39	Cum				
4	Providing, Preparing and Installing 6mm plywood in joint and (JDR)	18.60	sqm				
		Total A					
		Total B					
		Total Amount Rs. (A+B)					
		Contengency 3%					
		VAT 13%					
		Net Amount Rs.					

(Signature)
Majhagawa, Rupandehi

02/W/8/KRM/082/083

D.No:



Kotahimai Rural Municipality
Office of Kotahimai Rural Municipality Executive
Majhagawa, Rupandehi
Lumbini province
Bill Of Quantity

(Signature)
नवराज शर्मा
इन्जिनियर

Project Name: Amargani Rambriksh Ko ghar Dekhi Taulan ko ghar samma PCC Dhalan

Location :- KRM W.N. - 1

F.Y. :- 2082/083

Date: 2083/01/02

S.n.	Description of work	Quantity	Unit	Rate	Rate In Word	Amount	Remark
A PROVISIONAL SUMS							
1	Supply and fixing Hoarding Board	1.00	nos	2500.00	Two Thousand Five Hundred Only	2500.00	
2	Additional lab test work for quality control as per instruction of site Engineer	1.00	PS	10000.00	Ten Thousand Only	10000.00	
Total A						12500.00	
B CONSTRUCTION WORKS							
1	Loosening of the ground upto a level of 200-250mm below the sub-grade level and compacted in layers as per Drawing and Technical Specification (compacting original ground supporting sub-grade)(1003/1005)	536.85	sqm				
2	Providing and laying of PCC (Grade M 15) in Road complete as per Drawing and Technical Specifications(2000)	80.53	Cum				
3	Providing, Preparing and Installing 6mm plywood in joint and (JDR)	2.13	sqm				
Total B							
Total Amount Rs. (A+B)							
Contengency 3%							
VAT 13%							
Net Amount Rs.							

(Signature)
सतेन्द्र यादव
प्रमुख प्रशासकीय अधिकृत

Q.No: 03/W/8/KRM/082/083

Project Name: Patilija Adhuro Durga Mandir Nirman
Location :- KRM W.N. - 1



Kotahimai Rural Municipality
Office of Kotahimai Rural Municipality Executive
Majhagawa, Rupandehi
Lumbini province
Bill Of Quantities

F. Y. :- 2082/083
Date: 2083/02/12

S.n.	Description of work	Quantity	Unit	Rate	Rate in words	Amount	Remarks
1	Supply and fixing Standrad size of Hoarding Board and additional lab test Work As instruction of site Engineer .	1.00	PS	6500	Six Thousand Five Hundred Only.	6500.00	
2	PCC For RCC Work with (1:1.5:3)	5.00	cum				
3	Making Wooden form work for slab and floor including supply and selection of materials fixing, nailing according to drawings, applying Primer, placing separa- tors, dismantling forms and hauling upto 30 m distance	15.66	sqm				
4	Making Wooden form work including supply and selection of materials fixing, nailing according to drawings, placing separa- tors, dismantling forms and hauling upto 30 m distance (beam height upto 0.30m)	4.80	sqm				
5	Sai Wood Chaukhat	0.13	cum				
6	12.5mm cement plaster Work (1:6)	219.58	sqm				
7	2 Coat Emulsion painting	137.14	sqm				
8	Brick Soling in Sand -flat	19.40	sqm				
9	Flooring Work with 1:2:4 PCC gravel	4.64	cum				

सत्यमेव जयते

सत्यमेव जयते
प्रमुख प्रशासकीय अधिकारी

D.No: 03/2018/KRM/082/082




ಕರ್ನಾಟಕ ಸರ್ಕಾರ
ಸರ್ಕಾರಿ ಕಾರ್ಯಾಲಯ
ಬೆಂಗಳೂರು
ಸಾರ್ವಜನಿಕ ಕಾರ್ಯಾಲಯ

10	1.5" Sal Wood Fram Shutter	2.52	cum				
11	Procelain glazed tile for floor	16.40	sqm				
12	Procelain glazed tile for Wall	82.44	sqm				
13	Electrical All Complete Work as Per Instruction of site engineer.	1.00	LS				
14	Supply and Installation of 2.5 Ft. Hight Standrad Size of Rcc Bagh ko Murti With All Complete Work	2.00	LS				
15	Supply and Installation of 5 Ft. Hight Standrad Size of Rcc Durga Mata ko Murti With All Complete Work	1.00	LS				
16	Fixing torsteel reinforcement grade 1 in RCC work including cleaning, cutting, bending, placing in position and binding with binding wire all complete.	318.62	kg				
17	Brick Masonry Work in 1:6 c/s mortar	4.19	cum				

Total Amount Rs.				
VAT 13%				
Net Amount Rs.				


ಬಿ.ಎಸ್. ಶಂಕರ್
 ಇಂಜಿನಿಯರ್


ಸಿದ್ದೇಶ್ ಜಿ.ಎಂ
 ಪ್ರಮುಖ ಪ್ರಾಜೆಕ್ಟ್ ಅಧಿಕಾರಿ

A.No: 04/10/18/KRM/082/083



Office of Kotahimai Rural Municipality Executive
Majhagawa, Rupandehi
Lumbini province
Bill Of Quantity

(Signature)
Majhagawa
Rupandehi

Project Name: Jamuhi Dekhi Lu: Sa: Na: Pa. Ko Simana Ra Purnihwa Chawk Dekhi Sano Sipwa Samma Sadak Star Unnati
Location :- KRM W.N. - 1
F.Y. :- 2082/083
Date: 2083/01/02

S.n.	Description of work	Quantity	Unit	Rate	Rate In Word	Amount	Remark
A PROVISIONAL SUMS							
1	Supply and fixing Hoarding Board	1.00	nos	2500.00	Two Thousand Five Hundred Only	2500.00	
2	Additional lab test work for quality control as per instruction of site Engineer	1.00	PS	10000.00	Ten Thousand Only	10000.00	
Total A						12500.00	
B CONSTRUCTION WORKS							
1	Loosening of the ground upto a level of 200-250mm below the sub-grade level and compacted in layers as per Drawing and Technical Specification (compacting original ground supporting sub-grade)(1003/1005)	6075.00	sqm				
2	Providing and laying loose gravel on the surface.	44.35	cum				
3	Providing and laying of PCC (Grade M 15) in Road complete as per Drawing and Technical Specifications(2000)	54.68	Cum				
4	Providing, Preparing and Installing 6mm plywood in joint and (JDR)	13.67	sqm				
Total B							
Total Amount Rs. (A+B)							
Contengency 3%							
VAT 13%							
Net Amount Rs.							

(Signature)
Majhagawa
Rupandehi

D.No. 05/W/O/KRM/082/083




Kotahimai Rural Municipality
Office of Kotahimai Rural Municipality Executive
Majhagawa, Rupandehi
Lumbini province
Bill Of Quantities

Project Name: Wada No. 1 Swasthaya karyalay ma Bharayang Tatha Ramp Nirman
Location :- KRM W.N. - 1

F. Y. :- 2082/083
Date: 2083/02/12

S.n.	Description of work	Quantity	Unit	Rate	Rate in words	Amount	Remarks
1	Supply and fixing Standrad size of Hoarding Board .	1.00	PS	2500	Two Thousand Five Hundred Only.	6500.00	
2	Earthwork in Exavation	17.16	cum				
3	Brick Soling in Sand -flat	58.85	sqm				
4	PCC work With Gravel (1:3:6)	2.89	cum				
5	Brick Masonry Work in 1:6 c/s mortar	19.15	cum				
6	Fixing torsteel reinforcement grade 1 in RCC work including cleaning, cutting, bending, placing in position and binding with binding wire all complete.	305.73	kg				
7	PCC For RCC Work with (1:1.5:3)	2.70	cum				
8	Making Wooden form work including supply and selection of materials fixing, nailing according to drawings, placing separa- tors, dismantling forms and hauling upto 30 m distance (beam height upto 0.30m)	20.77	sqm				


Kotahimai Rural Municipality


सतिका राजवंश
प्रमुख प्रशासकीय अधिकारी

D.No. 05/W/Q/KRM/082/083



9	Construction of Embankment with Material obtained from Borrow pits Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications.	726.78	cum				
10	12.5mm cement plaster Work (1:6)	11.50	sqm				
11	Flooring Work with 1:2:4 PCC gravel	5.00	cum				
12	Providing and laying loose gravel on the surface	16.00	cum				
Total Amount Rs.							
VAT 13%							
Net Amount Rs.							

[Signature]
ಗವರಜಿ ಭಾಜಾನಿ
 ಇಂಜಿನಿಯರ್

[Signature]
ಸತೀಶ್ ಕುಮಾರ್ ರಾವ್
 ಪ್ರಮುಖ ಪ್ರಾ.ಸೇವಾಧಿಕಾರಿ
 ಪ್ರಮುಖ ಪ್ರಾ.ಸೇವಾಧಿಕಾರಿ ಅಧಿಕಾರಿ

06/12/20/81/KRM/082/083



Project Name:- Wada office Agadiko Bato saronhrai ra Marchawer Adarsna Ma. Vi. sadak gravel
Location :- KRM V./N. - 5

Kotahimai Rural Municipality
Office of Kotahimai Rural Municipality Executive
Majhagawa, Rupandehi
Lumbini province
Bill Of Quantities

F. Y. :- 2082/083
Date: 2083/02/11

S.N.	Description of work	Quantity	Unit	Rate	Rate in words	Amount	Remarks
1	Provisional Sum (Sign Board, Lab Test & others)		PS	15000.00			
	Total PS			15000.00			
2	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications.	492.00	Sqm				
3	Crusher Run Macadam Base. Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing, watering and compacting to form a layer of sub-base./Base course as per Drawing and Technical Specifications. By Mix in palce method. ii) for 45mm maximum size	73.80	Cum				
4	Construction of Embankment with Material obtained from Borrow pits Providing, laying, spreading and compacting embankment with borrow <i>material</i>	209.45	Cum				Sell available
5	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications. By mechanical means.	90.75	Cum				
Total without PS							
VAT 13%							
Total with VAT & PS							

PP

नगरपालिका
सुदूरपश्चिम प्रदेश

सुदूरपश्चिम प्रदेश
नगरपालिका

07/11/21 9/KRM/082/083



Kotahimai Rural Municipality
Office of Kotahimai Rural Municipality Executive
Majhnagawa, Rupandehi
Lumbini province

Bill Of Quantities

Project Name:- Thulo Majhnagawa Madarsha dekhni Mui sadak sano majhnagawa hudai lodhpurwa samma sadak gravel
Location :- KRM W.N. - 5

F.Y. :- 2082/083
Date:2083/02/11

S.N.	Description of work	Quantity	Unit	Rate	Rate in words	Amount	Remarks
1	Provisional Sum (Sign Board, Lab Test & others)		PS	10000.00			
	Total PS			10000.00			
2	Scarifying the existing granular road surface by Mannual means to a depth of 50 mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications.	1218.00	Sqm				
3	Crusher Run Macadam Base. Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing , watering and compacting to form a layer of sub-base/Base course as per Drawing and Technical Specifications. By Mix in palce method. ii) for 45mm maximum size	182.65	Cum				
Total without PS							
VAT 13%							
Total with VAT & PS							

नगरपालिका
सुदूरपश्चिम प्रदेश

सतेन्द्र यादव
प्रमुख प्रशासकीय अधिकृत

08/W/O/KRM/082/083



Kothimai Rural Municipality
Office of Kothimai Rural Municipality Executive
Majhagawa, Rupandehi
Lumbini province
Bill Of Quantities

(Signature)
नवराज मण्डल
इन्जिनियर

Project Name:- Gaupalikako Sabhahall Panchayat, Kothimai, Rupandehi, Kailash bato nirman tatha gravel ra Lodhpurwa krishibato sadak gravel
Location :- KRM W.N. - 5

F.Y. :- 2082/083
Date:2083/02/11

S.N.	Description of work	Quantity	Unit	Rate	Rate in words	Amount	Remarks
1	Provisional Sum (Sign Board, Lab Test & others)		PS	15000.00			
	Total PS			15000.00			
2	Scarifying the existing granular road surface by Manual means to a depth of 50 mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications.	1564.50	Sqm				
3	Construction of Embankment with Material Deposited from Roadway Cutting Providing, laying, spreading and compacting embankment with roadway cutting material and compact to the required density as per Drawing and Technical Specifications. (With machine)	113.99	Cum				
4	Construction of Embankment with Material Deposited from Roadway Cutting Providing, laying, spreading and compacting embankment with roadway cutting material and compact to the required density as per Drawing and Technical Specifications. (With machine)	202.65	Cum				
5	Construction of Embankment with Material obtained from Borrow pits Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications.	63.00	Cum				
6	Providing and laying granular sub-base on Road Pothole and Maintenance Work (No compaction)	101.33	Cum				
7	Road way Excavation in all types of soil by Mechanical Means as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer.	12.03	Cum				
8	Providing and Laying Reinforced Cement Concrete Flush jointed Pipe for culverts Providing and Laying Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications. 600 mm internal dia.	5.00	m				
9	Providing and Laying Reinforced Cement Concrete Flush jointed Pipe for culverts Providing and Laying Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications. 300 mm internal dia.	5.00	m				
10	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications. By mechanical means.	133.35	Cum				
	Total without PS						
	VAT 13%						
	Total with VAT & PS						

(Signature)

(Signature)
नवराज मण्डल
इन्जिनियर